| | | | | Fastener Schedule ² | | | DF/SP | | | | | |
|---|-----------|------|-------|--------------------------------|------|-------|-------------|------------------------|------|------|---------------------|--|
| | | | | He | ader | Joist | | Allowable Loads (Lbs.) | | | | |
| Joist | MiTek USP | Ref. | Steel | | | | | Floor | Roof | | Uplift ¹ | |
| Size | Stock No. | No. | Gauge | Qty | Туре | Qty | Type | 100% | 115% | 125% | 160% | |
| 2 x 4 | CLPBF | | 18 | 12 | 10d | 6 | 10d x 1-1/2 | 1340 | 1340 | 1340 | 195 | |
| 1) Uplift loads have been increased 60% for wind or seismic loads; no further increase shall be permitted. 2) NAILS: $10d \times 1-1/2$ nails are 0.148 " dia. $\times 1-1/2$ " long, $10d$ nails are 0.148 " dia. $\times 3$ " long. | | | | | | | | | | | | |