

Installation Type	Fastener Schedule ²					DF Allowable Loads (Lbs.)							
	Header			Joist		Solid Sawn Header				2-Ply, 2x Wall Top Plate			
	Top Qty	Face Qty	Type	Qty	Type	Download			Uplift ¹ 160%	Download			Uplift ¹ 160%
						100%	115%	125%		100%	115%	125%	
Without 5/8-in gypsum wallboard or structural sheathing	6	--	10d	6	10d x 1-1/2	2240	2240	2240	180	2045	2045	2045	180
		2							380				380
After (1) layer of 5/8-in gypsum wallboard is installed	6	--	10d	6	10d x 1-1/2	2400	2400	2400	180	2400	2400	2400	180
		2							380				380
After (2) layers of 5/8-in gypsum wallboard are installed	6	--	10d	6	10d x 1-1/2	2400	2400	2400	180	2400	2400	2400	180
		2							380				380
Two-sided after (2) layers of 5/8-in gypsum wallboard are installed (min. 2x6 wall)	6	--	10d	6	10d x 1-1/2	2400	2400	2400	180	2400	2400	2400	180
		2							380				380
After (1) layer of structural sheathing & (1) layer of 5/8-in gypsum wallboard is installed	6	--	10d	6	10d x 1-1/2	2400	2400	2400	180	2400	2400	2400	180
		2							380				380

1) Uplift Loads have been increased 60% for wind or seismic loads; no further increase shall be permitted.

2) **NAILS:** 10d x 1-1/2 nails are 0.148" dia. x 1-1/2" long, 10d nails are 0.148" dia. x 3" long.