HANGER AND CONNECTOR SCHEDULE

- 1. All WOOD FRAMING CONNECTORS shall be MiTek "USP STRUCTURAL, CONNECTORS", SIMPSON "STRONG-TIE" or equivalent and shall be in accordance with the following schedule unless specifically noted otherwise.
- 2. Refer to MiTek "USP STRUCTURAL CONNECTORS" OR SIMPSON product catalogs for proper installation.
- 3. HARDWARE not referenced in the following schedule shall be installed to framing with fasteners per manufacturer's recommendations for maximum capacity.
- 4. NAILS FOR CONNECTORS should be installed in all round holes. If MAX is noted on the framing plan, then install nails in all holes including diamond shaped holes. Full length common nails should be installed in all slant nailed hangers to insure nail penetration into the supporting member.

Application Type			Factoria
Application Type and Image	Simpson	MiTek USP	Fastener Schedule
Top Mount Single ply I-Joist to Wood Framing	Ompoon	MITTER GOT	Solicatio
or Nailer	ITS	THO	11-7/8"-in and shallower I-Joists. 10d Common Nails into Header, 10dx1-1/2" into Joist.
	MIT	TFL	14-in or deeper I-Joists. 10d Common Nails into Header, 10dx1-1/2" into Joist.
	MIT	TFI	2-3/8" or wider I-Joists. 16d Common Nails into Header for TFL, 10dx1-1/2" into Joist.
Top Mount Single ply 2X Joist to Wood Framing or Nailer	JB	HL	2x14 and shallower 2X Joists. 16d Common Nails into header.
Top Mount Multi-ply 2X or 3X beams to Wood Framing or Nailer	HUTF	HDO	(2,3,4 Ply) 2X lumber with 10d Common nails.
	HW	KHW	6X & 8X Timber with 10d Common Nails.
	HWU	PHXU	3-1/2" width or smaller structural composite or glulam EWP members. 10d Common Nails.
	HWU	PHXU	5-1/8" width or wider structural composite or glulam EWP members. 16d Common Nails.
Face Mount Single ply I-Joist to Wood Framing or Nailer	IUS	THF	16-in or shallower I-Joists. 10d Common Nails.
Face Mount Single ply 2X Joist to Wood Framing or Nailer	LUS	JUS	2x12 or shallower 2X lumber. 10d Common Nails
Face Mount Multi-ply 2X beams and 3X,4X,6X, and 8X and EWP lumber to Wood Framing or Nailer	HU	HD	(2,3,4 Ply) 2X lumber and 6X lumber with 16d Common nails into Header and 10d Common nails into joist.
	HU	HD	8X lumber with 16d Common nails.
	HU	HD	Structural composite or glulam EWP members. 16d Common Nails.
Top Mount 2X Joist to Nailer	JB	SW	10d x 1-1/2" Nails

Top Mount Multi-ply 2X or 3X or larger beams to Nailer	WNP	SWH	(2 Ply) 2x6 and deeper lumber with 10d x 1-1/2" Nails
	W	SWH	4x6-in or shallower lumber with 10d x 1-1/2" Nails
	BA	ВРН	4x8-in or deeper lumber with 10d x 1-1/2" Nails
	HW	KHW	4X, 6X, 8X Lumber attached to 3X mimimum letter. 16d x 2-1/2" Nails to nailer. 10d Common to joist.
	HWU	PHXU	Structural composite or glulam EWP members. 16d Common Nails to nailer. 10d x 1-1/2" to Joist. 4X Minimum Nailer.
Top Mount Single ply I-Joist to structural steel			
	ITS	THO	11-7/8"-in and shallower I-Joists. #10 Self Tapping screws into beam, 10dx1-1/2" into Joist.
	MIT	TFL	14-in or deeper I-Joists. #10 Self Tapping screws into beam, 10dx1-1/2" into Joist.
Top Mount Single ply 2X to Structural Steel			
	LB	SW	#10 Self Tapping Screws. 10d x 1-1/2" Nails into Joist
Top Mount Multi-ply 2X or 3X beams to Structural Steel	В	HDO	3X and 4X Lumber with #10 Self Tapping Screws, 10d Common Nails into Joist
	HW	KHW	6X and 8X Lumber with #10 Self Tapping Screws. 16d Common Nails into joist.
	НВ	НВРН	3-1/2" width or smaller structural composite or glulam EWP members. #10 Self Drilling Screws or weld to Beam. 16d Common Nails into Joist.
	ННВ	КННВ	5-1/8" width or wider structural composite or glulam EWP members. #10 Self Drilling Screws or weld to Beam. 16d Common Nails into Joist.
Mudsill Anchor	MASA	FA4	10d x 1-1/2" Nails
Holdown-Embedded Strap	STHD10	STAD10	Installed directly to Framing, 10d x 1-1/2", 10d Common or 16d Sinker. Installed over sheathing
	STHD14	STAD14	with 10d Common or 16d Sinker Nails
Holdown-Nailed w/Anchor Bolt	HTT4	HTT45	Install Directly to Framing with 10d Common or 16d
	HTT5	HTT45	x 2-1/2" Pnuematic
Holdown-Screwed or Bolted w/Anchor Bolt	HDU2	PHD2A	
	HDU4	PHD4A	Install Directly to Framing with Manufacturer Provided Screws. Retighten nuts before closing walls.
	HDU5	PHD5A	
	HDU8	UPHD8	
	HDU11	UPHD11	
	HDU14	HPHD14	leadalla viith Deli-
	HD19	TD15	Installs with Bolts

Straps	01107015	01407015	T
Straps	CMSTC16	CMSTC16	-
	CMST14	CMST14	-
	CMST12	CMST12	Installed directly to Framing, 10d x 1-1/2" with 10d
	CS22	RS300	Common or 16d Sinker. Installed over sheathing
• • • • • • • • • • • • • • • • • • • •	CS20	RS250	with 10d Common or 16d Sinker Nails
/	CS18	RS200	
	CS16	RS150	
	CS14	RS14-100	
Framing Clips	A35	MPA1	Installed directly to Framing, 8d x 1-1/2" with 8d Common or 16d Sinker. Installed over sheathing with 8d Common or 16d Sinker Nails
	LTP4	MP4F	
Hurricane Ties	H1	RT15	Installed directly to Framing, 8d x 1-1/2" with 8d Common or 16d Sinker. Installed over sheathing with 8d Common or 16d Sinker Nails
Post Caps	PC	PCM	
	EPC	EPCM	Installed with 16d Common or 16d x 2-1/2" Nails.
	ВС	С	
Post Bases	РВ	WE	Installed with 16d Common or 46d v 2.4/2" Note:
	PBS	WAS	Installed with 16d Common or 16d x 2-1/2" Nails.